


Advantech AE Technical Share Document

Date	2019/4/29	Release Note	□ Internal ■ External
Category	■ FAQ □ SOP	Related OS	WIN7
Abstract	Windows 7 Device Manager Shows Yellow exclamation Mark with NVIDIA RTX		
	GPUs.		
Keyword	WIN7, Yellow Mark, RTX, NVDIA.		
Related Product	The Platforms which use RTX GPUs with WIN7.		

■ Problem Description:

Windows 7 Device Manager Shows Yellow exclamation mark with NVIDIA RTX GPUs.



Problem Analysis:

Windows 7 does not support the eXtensible Host Controller Interface (xHCI), which is required for proper operation of the USB-C port. Similarly, the USB-C Port Policy Controller (PPC) driver is not supported on Windows 7. Thus, the yellow bang provides an alert that not all USB-C capabilities are accessible..



■ Brief Solution:

The lack of xHCl and USB-C PPC drivers support means that the USB-C port is not able to deliver the necessary power and data signals required to run head mounted displays (HMDs) for virtual reality (VR) applications. However, the display signals coming out of the USB-C port are not affected. Despite the yellow bang alert, the USB-C port can still be used to drive a display.

■ Reference:

1. NVDIA:

https://nvidia.custhelp.com/app/answers/detail/a id/4754/~/windows-7-device-manager-sh ows-yellow-bang-with-nvidia-rtx-gpus

■ Contact Window and File Link:

If you have any questions, please contact Dennis89.Huang #1241 You can download this file on Global AE SharePoint - FAQ